Listing of Claims:

- 1. (previously presented) A frame element for a monopolar stack, comprising:
 - a plurality of recesses for receiving ribs of plate elements arranged to form a stack, and/or
 - a plurality of perforations for passing therethrough ribs of plate elements which are arranged to form a stack.
- (previously presented) A frame element according to claim 1, comprising perforations for passing therethrough ribs of the plate elements arranged to form a stack, wherein the frame element is provided at one side with a structure which is electrically conductive in portions and which supports a monopolar wiring of the plate elements arranged to form the stack.
- (previously presented) A frame element (20; 220) according to claim 2, wherein
 the structure (25; 225) which is electrically conductive in portions comprises a
 regular pattern.
- 4. (previously presented) A frame element according to claim 2, comprising:
 - a printed circuit board on which the structure is formed that is electrically conductive in portions.
- 5. (previously presented) A frame element according to any claim 1, comprising:
 - mounting means for two end plates which complete the stack of plate elements at hoth sides

- (previously presented) A frame element according to any one of claim 1, comprising at least one channel for fluid conduction along a stack axis of the monopolar stack.
- (previously presented) A method for producing a fuel cell stack, comprising the steps of:

arranging plate elements in a stack arrangement;

pre-tensioning the plate elements;

laterally attaching frame elements according to claim 1 on the stack so that the recesses and/or the perforations of the frame elements receive ribs of the plate elements:

offsetting the pretension.

- (previously presented) A method according to claim 7, wherein prior to the
 offsetting of the pretension the ribs of the plate elements are soldered with the
 frame elements.
- 9. (previously presented) A frame element according to claim 3, comprising:

a printed circuit board on which the structure is formed that is electrically conductive in portions.

10. (previously presented) A frame element according to claim 2, comprising:

mounting means for two end plates which complete the stack of plate elements at both sides.

(previously presented) A frame element according to claim 3, comprising:

mounting means for two end plates which complete the stack of plate elements at both sides.

- 12. (previously presented) A frame element according to claim 4, comprising:
 - mounting means for two end plates which complete the stack of plate elements at both sides.
- (previously presented) A frame element according to claim 2, comprising at least one channel for fluid conduction along a stack axis of the monopolar stack.
- (previously presented) A frame element according to claim 3, comprising at least one channel for fluid conduction along a stack axis of the monopolar stack.
- (previously presented) A frame element according to claim 4, comprising at least one channel for fluid conduction along a stack axis of the monopolar stack.
- (previously presented) A frame element according to claim 5, comprising at least one channel for fluid conduction along a stack axis of the monopolar stack.
- (previously presented) A method for producing a fuel cell stack, comprising the steps of:

arranging plate elements in a stack arrangement;

pre-tensioning the plate elements:

Application No. 10/538,601 Response dated May 12, 2009 to action dated April 20, 2009

laterally attaching frame elements according to claim 2 on the stack so that the recesses and/or the perforations of the frame elements receive ribs of the plate elements:

offsetting the pretension.

 (previously presented) A method for producing a fuel cell stack, comprising the steps of:

arranging plate elements in a stack arrangement;

pre-tensioning the plate elements;

laterally attaching frame elements according to claim 3 on the stack so that the recesses and/or the perforations of the frame elements receive ribs of the plate elements:

offsetting the pretension.

 (previously presented) A method for producing a fuel cell stack, comprising the steps of:

arranging plate elements in a stack arrangement;

pre-tensioning the plate elements;

laterally attaching frame elements according to claim 4 on the stack so that the recesses and/or the perforations of the frame elements receive ribs of the plate elements:

offsetting the pretension.

 (previously presented) A method for producing a fuel cell stack, comprising the steps of:

arranging plate elements in a stack arrangement;

pre-tensioning the plate elements;

laterally attaching frame elements according to claim 5 on the stack so that the recesses and/or the perforations of the frame elements receive ribs of the plate elements:

offsetting the pretension.